

Product Listing	Est Duration	Approximate Lead Times (weeks)																													
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
Piling (Bored Piers) *	4 weeks	█	█	█	█																										
Piling (Screw) *	2 weeks	█	█																												
Piling (Sheet) *	3-4 weeks	█	█	█	█																										
Piling (pre-cast) *	3-4 weeks	█	█	█	█																										
Structural steel frames *	12 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Pre-cast Panels *	5 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Anchors	2 weeks	█	█																												
Formwork - Jump Form / Slip Form *	6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Formwork - Conventional or Bondek	1 week	█																													
Formwork - Table Forms	2 weeks	█	█																												
Edge Protection - Screens	6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Roof/Cladding - insulated sheeting	3-4 weeks	█	█	█	█																										
Roof/Cladding - basic profiled metal	2-4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Roof finishes - overseas products	4-8 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Louvres	4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Curtain walling systems *	12 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Glazing (Approval & Manufacture) *	5-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Wall / Ceiling - Framing / Plasterboard	2 days	█																													
Door & Frames (Incl Fire Rated Doors) *	6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Specialist Doors *	10-12 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Door / Sundry Hardware	5-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Toilet Partitions	6-8 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
General joinery (laminated) *	3-4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
General joinery (2 pac) *	5-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Specialist joinery *	8-10 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Passenger lifts (1-20 Floors) *	24-26 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Passenger/Commercial lifts (20+ Floors) *	26-28 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Escalators & Travelators *	20 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Mech Shop Drawings - Traditional	4-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Mech Shop Drawings - D & C	8-10 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Ductwork	2-4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Air Handling Units	6-10 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
VAV units	2-4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Chillers	12-14 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Electrical Shop Drawings	2-4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Distribution Boards *	4-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Main Switch Boards *	12-14 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Generators (Standard) & UPS	4-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Transformer	12-16 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Security systems (incl approvals)	4-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Fire Shop Drawings	1-2 weeks	█	█																												
Sprinklers	1-2 weeks	█	█																												
Fire Pumps	4-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
FIP - Fire Indicator Panel	4-6 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Flooring - Vinyl & Tiles (Aust)	1-2 weeks	█	█																												
Workstations & Chairs (Aust)	4 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
Workstations & Chairs (Import)	12 weeks	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█

\* includes shop drawings

**Disclaimer :**

This information is provided with the compliments of RCP for your personal information and use. RCP always recommends that you seek professional advice in relation to your particular project or circumstances before making any decisions. Whilst calendar information is correct at the time of printing, RCP is not responsible for changes Copyright © 2014 RCP ACN 010 285 757

**RCP SERVICES**

Project Programming & Scheduling  
Project Management  
Development Management  
Delay Claim Advisory

**RCP OFFICES**

**Brisbane** T: 07 3003 4100  
**Sydney** T: 02 8084 9436  
**Melbourne** T: 03 9038 1772  
**Townsville** T: 07 4721 0833

w: [www.rcp.net.au](http://www.rcp.net.au)  
e: [rcp@rcp.net.au](mailto:rcp@rcp.net.au)